


VillageWaters

VillageWaters WP3 workshop

Pilot evaluation - Svētciems

Loreta Urtāne, Aleksejs Pertsovs Univerity of Latvia (PP6)

Information about the pilot - situation







Information about the pilot - territory

- Definition of the territory: WWTP of Svētciems, Salacgrīva parish
- Water bodies on the territory: Svētupe river, salmonid waters
- Protected Areas: in territory of Northern Biosphere Reserve
- Owner: Salacgrīva Municipality
- Operator: Salacgrīva Ūdens, municipal utilities company



Information about the pilot – loads (1/3)

- Population of Svētciems as per 2016: 427
- Connected to municipal water supply system: 408
- Connected to municipal wastewater evacuation system: 361
- Public institutions:
 kindergarten 33 children, 9 nursery teachers
 library 2 librarians
- Industries: none
- Average water consumption: 85 l/person/day
- Daily hydraulic load on WWTP: 30.7 m³



Information about the pilot – loads (2/3)

Influent wastewater analyses March 2017

| Pollutant | Concentration | Units of measure |
|--------------------|---------------|------------------|
| BOD ₅ | 140 | mg/l |
| COD | 420 | mg/l |
| Suspended solids | 1 260 | mg/l |
| N _{total} | 56 | mg/l |
| P _{total} | 7.5 | mg/l |

Average Potable water consumption: 30.7 m³/day

Daily hydraulic load on WWTP: 41.6 m³/day



Information about the pilot – loads (3/3)

Daily load on WWTP, according to influent wastewater analyses March 2017

| Pollutant | Concentration | Units of measure |
|--------------------|---------------|------------------|
| BOD ₅ | 5.8 | kg/day |
| COD | 17.5 | kg/day |
| Suspended solids | 52.5 | kg/day |
| N _{total} | 2.3 | kg/day |
| P _{total} | 0.3 | kg/day |

Average Potable water consumption: 30.7 m³/day

Daily hydraulic load on WWTP: 41.6 m³/day




Information about the pilot – old WWTP (1/5)

- Year of construction: 1984, $Qn = 2 \times 100 \text{ m}^3/\text{day}$
- Type of WWTP: 2 × BIO100 aeropacks + biological polishing ponds
- Treated water discharge: Svētupe river
- Power consumption: 123 kWh/day (air blower only)
- Processing of excessive sludge: evacuated to Salacgrīva WWTP



Information about the pilot – old WWTP (2/5)



VillageWaters

Information about the pilot – old WWTP (3/5)

Effluent water after aeropack, according to analyses March 2017 (mg/l)

| Pollutant | Concentration after aeropack (mg/l) | Efficiency (%) |
|--------------------|-------------------------------------|-------------------|
| BOD ₅ | 72.8 | 48 |
| COD | 176.4 | 58 |
| Suspended solids | 264.6 | 79 |
| N _{total} | 42.56 | 24 |
| P _{total} | 6.8 | 9 |



Information about the pilot – old WWTP (4/5)

Effluent water after polishing pond, according to analyses March 2017 (mg/l)

| Pollutant | Concentration after aeropack (mg/l) | Efficiency (%) |
|--------------------|-------------------------------------|-------------------|
| BOD ₅ | 3.4 | 95 |
| COD | 43 | 76 |
| Suspended solids | 5.2 | 98 |
| N _{total} | 3.6 | 92 |
| P _{total} | 4.3 | 37 |



Information about the pilot – old WWTP (5/5)

Comparing the efficiency of aeropacks and polishing pond

| Pollutant | Efficiency of aeropack (%) | Efficiency of polishing pond (%) |
|--------------------|----------------------------|----------------------------------|
| BOD ₅ | 48 | 95 |
| COD | 58 | 76 |
| Suspended solids | 79 | 98 |
| N _{total} | 24 | 92 |
| P _{total} | 9 | 37 |



The problem


- Aeropack does not provide sufficient treatment efficiency
- Polishing pond is main treatment unit, it is overloaded and there is a big risk of one-shot flushing of the pollutants, collected in the pond to Svetupe river





Proposed solution – step 1


VillageWaters



Proposed solution – step 2

Baltic Sea Region

VillageWaters



Expected results

- Estimated volume of investments: 72 000 EUR
- Year of construction: 2018, Qn = 40 m³/day
- Type of WWTP: 1 × aeropacks with extended primary clarifier + biological polishing ponds (old ones treated)
- Treated water discharge: Svētupe river
- Power consumption: 70 kWh/day
- Processing of excessive sludge: evacuated to Salacgrīva WWTP
- Lifecycle: **30 years**
- Social impact: decreasing of WW cost



Progress as per February 2018

- Performed feasibility study
- WWTP is under development of design papers
- Designer company "EkoStandarts Tehnologijas"